

ORNL Liquid Salt Test Facility

Presented by:

Kevin Robb robbkr@ornl.gov

Reactor and Nuclear Systems Division

Thermal Hydraulics & Irradiation Engineering Group

October 15-16, 2015



Thermal Hydraulic and Related Technology Challenges

- **General:** high temperature, material selection
- **Operations:** maintenance, line plugging, unexpected cooling
- **Endurance & reliability:** creep & fatigue, pumps, valves, seals
- **Salt prep. & handling:** mixing, cleaning, freeze/thaw/transfer
- **Instrumentation:** temperature, material compatibility, non-intrusive
- **Uncertainty:** correlations, salt properties, I&C
- **Special considerations:** beryllium, tritium, special alloys, etc.

- Many challenges were overcome for MSRE; however, challenges remain for commercialization


ORNL Liquid Salt Test Loop (LSTL)

Initial Goals:

- 1) Provide infrastructure (operational knowledge and equipment) to test high temperature salt systems
 - 2) Develop non-intrusive inductive heating technique that can be used for thermal/fluid experimentation
 - 3) Measure heat transfer characteristics in a molten salt cooled pebble bed
 - 4) Demonstrate the use of Silicon Carbide (SiC) as a structural material for use in molten salt systems
- Started with ORNL internal investment
 - Currently supporting cooperative research with SINAP

LSTL - General Layout

- Storage tank
 - Long term salt storage allows re-solidification
- Pump sump tank
 - Sump type centrifugal pump
- SiC test section (pebbles)
 - Pebble heat transfer
- Surge tank
- Forced draft air cooler
- Trace heating and gas supply system
- A range of I&C



LSTL - General Specs

A versatile test facility

Salt	LiF-NaF-KF (FLiNaK)
Salt volume	~72 liters
Operating Temperature	up to 700°C
Flow rate	≤ 4.5 kg/s ~3.5 m/s (1in ID)
Operating pressure	~Atmospheric
Material of construction	Inconel 600
Operating run time life	2+ years
Primary piping ID	1.05 in
Heating	Trace: ~20 kW Induction: 200 kW
Heat rejection	Air-cooled heat exchanger



LSTL - Testing Phases

- 1st phase
 - Shakedown testing (seals, pump, I&C, HX)
 - Pebble bed heat transfer
- 2nd phase
 - Pump performance characterization
 - Corrosion in flowing salt (DOE-NE IRP)
- 3rd phase
 - To be decided

LSTL - Pebble bed testing


- Initial testing focused on pebble bed heat transfer
 - Important to predict peak pebble temperature during normal operation and transients

Power	≤ 200 kW total ≤ 1.28 kW/pebble
Fluid ΔT	$\leq 20^\circ\text{C}$
Pebble Reynolds Number	≤ 2600
Pebbles	~ 500
Diameter	15 cm - Bed 3 cm - Pebble
Bed height	24 cm non-heated (top) 24 cm heated 24 cm non-heated (bottom)
Thermocouples	2 in pebbles 2 near pebbles 1 inlet 2 outlet


Top Screen



3 cm Pebbles



Bottom Screen




Large SiC Tube



Component Development & Testing Pumps




- Objectives:
 - Characterize the performance of the existing pump
 - Improve impeller & volute design and test for improvement
 - Develop selection & design guidance for salt pumps
- Status:
 - Using advanced simulation to aide impeller and volute design
 - Developing cold shakedown test stand
 - FY16 3Q, modify LSTL to develop pump curves
- Collaborative R&D with SINAP



Component Development & Testing


Ultrasonic Flowmeter

- Objectives:
 - Develop and test process to calibrate clamp-on ultrasonic flow meters
- Status:
 - Shakedown testing on water loop
 - Developed salt calibration test stand for well controlled & measured flow
 - Detailed uncertainty analysis
- Collaborative R&D with SINAP



Component Development & Testing Additional

- Optical access, experimental techniques, natural circulation heat transfer^[1]
 - Exploration of window access, Photography, IR Camera, and LDV
 - Natural circulation heat transfer data
- Fluidic diode^[2]
 - A ‘passive leaky check valve’
 - Water testing and CFD modeling
- SiC-Metal Flange
 - Testing of flange, bolting, and gasket assembly procedure




[1] G. L Yoder, et al., “Liquid Fluoride Salt Experiment Using a Small Natural Circulation Cell,” ORNL/TM-2014/56, April 2014.

[2] G. L Yoder, et al., “Vortex Diode Analysis and Testing for Fluoride Salt-Cooled High-Temperature Reactors,” ORNL/TM-2011/425, Sept. 2011.

Salt Cleanup Facility

- Removes trace impurities from salt
 - Enabling facility for salt studies
 - Batch process, cleans 150 kg of salt in one week
- Significant capability
 - Uses HF, H₂ and Ar
 - Large 2 m Nickel crucible
- Development supported by DOE-NE
- Currently developing smaller scale capability for Beryllium containing salts



Summary

- We need to address a variety of technology R&D and demonstration for reactor commercialization
 - Many common issues between FHR and MSR reactor classes
- The Liquid Salt Test Loop provides a versatile testing platform for a range of development needs
 - Planned testing includes shakedown, heat transfer, pump performance, and corrosion tests
 - Future tests could include:
 - Development: valve/seals, heat exchangers, etc.
 - Demonstration: advanced I&C, component endurance
 - Validation: tests for code benchmarks

Backup

LSTL – Instrumentation

Thermocouples	Numerous, (7 in bed)
Pressure	1 in salt 2 in gas spaces
Flow rate	Ultrasonic flow meter
Level	1 radar level in sump tank Heated thermocouple arrays 1x sump tank 1x surge tank

